

City of Sundance
Street Improvement Project
2018

BID SHEET

The unit prices times the actual quantities placed for each of the bid items is the total compensation for the street improvement work in the City of Sundance, Wyoming. No bid bond is required, but the successful low bidder will provide the City a performance bond in the amount of the total bid price within ten days of notice of award. All work must be completed by October 15, 2018.

The construction materials and contract work will be in accordance with the WYDOT Standard Specifications for Road and Bridge Construction, Current Edition. The contractor will provide their commercial asphalt mix design (1/2" maximum size aggregate) to the Mayor for his review and approval at least ten days prior to commencing paving operations. No lime is required in this asphalt mix.

The asphalt paving will be paid by the ton "complete in place" including but not limited to street cleaning, tack, traffic control, mobilization, cleanup, overhead and profit.

All paving overlay thickness will be 2" or as noted.

90% payment will be made lump sum following completion of all work. The remaining 10% will be paid when all cleanup is complete, all documents have been submitted, and the Mayor is satisfied with the completed work.

SUMMARY OF WORK

Work Site	Length	Paving	Width	Thickness	Milling*
<u>Refer to attached map</u>	<u>Feet</u>	<u>Tons</u>	<u>Feet</u>	<u>Inches</u>	<u>Square yards</u>
1.3rd Street	450	230	42	2	
2. Hillcrest	625	340	45	2	1600
3. Mt. View Drive	500	200	32	2	1400
4. 7th Street	320	100	26	2	
5. 11th Street	225	75	26	2	
6. West Ryan	410	130	25	2	
7. 3rd Street	310	50	12	2	420 West Curb
8. Main Street	300	50	12	2	415 South Curb
9. High Mile	450	200	35	2	
Totals		1375			3835

*** All transverse construction joints shall be milled prior to paving.**

Note #1: All or individual quantities of work may be adjusted by the City to fit the funds allocated for the work.

Note #2: Work site #7 and #8 involves milling existing pavement to a depth of 2" below the top edge of the concrete gutter and 2" below the existing pavement 12' into the street. The milled areas will be repaved. No other paving will be done in these work areas.

Note #3: Work site #2 and #3 involves milling existing pavement at the curbs to a depth of 2" below the top of the gutter concrete and tapered to top of existing pavement 12' into the roadway. The entire roadway to receive a 2" overlay.

Note #4: All millings will be retained by the City and contractor will place them in an area designated by the City.

The only documents pertaining to this work is the city map provided, advertisement for bids, WYDOT Standard Specifications current edition and this bid sheet. The contractor will be required to obtain a contractor's license from the City of Sundance. The contractor may subcontract portions of the work not to exceed 50% of the total contract amount with the written approval of the Mayor. The Mayor may choose to designate a representative to oversee and coordinate day-to-day construction activities.

BID SCHEDULE

Bid Item	Unit	Quantity	Unit Price	Total Item Cost
HPM B P (1/2"max) Street Paving	Ton	1375		
Pavement Milling	S.Y.	3835		
Total Bid Price				\$

Bid Submitted by:

Contractor

Signature

Date

Acceptance by the City of Sundance:

Mayor

Date