

**Pioneer Park Tree Felling, Bucking, and Removal Project**

Work item	Work requirements
<b>Bid Item Number 1 -- Hazard Trees (HT)</b>	
HT 1	Standard Specifications 1 and 2. Leave no material in the open camp area clearing.
HT 2	Standard Specifications 1 and 2. Cut all material under 4" in diameter into 2' lengths. Leave no material in the road.
HT 3	Standard Specifications 1 and 2.
HTs 4 and 5	Standard Specifications 1 and 2. Pull all material 10' from road edge.
HTs 6 and 7	Standard Specifications 1 and 2. Pull all material back 20' from edge of campsite clearing.
HT 8	Standard Specifications 1 and 2. Clear trail 5' from each side of trail edge.
HT 9	Standard Specifications 1 and 2. Clear trail 5' from each side of trail edge.
HTs 10, 11, 12	Standard Specifications 1 and 2. Clear trail 5' from each side of trail edge.
HT 13	Bring hanging branch to ground and remove from picnic site
HT 14 & 15	Standard Specifications 1 and 2.
<b>Bid Item 2 -- Blow Down Sites</b>	
Site A	Standard Specification 2
Site B	Standard Specification 2 Remove material from campsite clearing.
Site C	Standard Specification 2 Cut existing high stump. Pull material back 10' from road. Clear trail 5' from each side of trail edge.
Site D	Standard Specification 2

<b>Pioneer Park Tree Felling, Bucking, and Removal Project</b>	
Work item	Work requirements
	Clear trail 5' from each side of trail edge.
Site E	Standard Specification 2
Site F	Standard Specification 2 Cut existing stump
Site G	Standard Specification 2
Site H	Standard Specification 2
Site I	Standard Specification 2
<b><u>Bid Item 3 -- Clearing</u></b>	
Remove up to 60 trees, including stumps and slash, as flagged in the field. Site shall be graded for use as a picnic and parking area. Work shall be coordinated with Best Management Practices (BMPS) for erosion and sediment control	
<b><u>Standard Specification 1</u></b>	
Cut and drop hazard trees to ground.	
<b><u>Standard Specification 2</u></b>	
A. Cut base of trees at root wad or no greater than 1" from ground level.	
B. All pieces greater than 5" in diameter must be cut to lie flat on the ground and bucked to length no greater than 8 feet long.	
C. All pieces less than 5" in diameter must be lopped and scattered to lie no higher than 18" from the ground	
<b>Note:</b> Individual hazard trees are marked and numbered with an orange paint "X" and orange flagging; blow down sites are marked and numbered with orange paint spots and orange flagging. Clearing trees are marked with pink flagging.	